

BANK PROTECTION ALONG RIGHT BANK OF PANCHANOI RIVER
FROM TO OLD MATIGARA ROAD TO KABI SUKANTA SCHOOL, SILIGURI

SL	Item Description	Qty	Unit	Rate	Amount
1	Earth work in excavation of foundation trenches in all sorts of soil (including mixed soil but excluding stoney and morrum soil) including removing spreading or stacking the spoils within lead of 150 metres as directed and including trimming the sides of trench, leveling, dressing and ramming the bottom, bailing or pumping out water etc. as required complete as per direction of Engineer-in-charge				
	By Mechanical means (Using suitable Excavator)				
	a) Depth upto 3 metre				
	i) Work with pumping out water	2025.00	CUM	51.2	103680.00
2	Providing and laying cement concrete (1:3:6) with or without reinforcement in any part of well, pier, abutment, wing wall, drop wall, with approved bazree of approved type 45mm to 22.4mm size with screening and cleaning of aggregate and sand as necessary, curing in water all complete.	200.00	CUM	2272.23	454446.00
3	Providing form work and staging including hire and labour charges for the same as required for foundation concrete works of depth not exceeding 500 mm and for concrete works in vertical faces of parapet curb, road curb, cable tray, cable tray cover so as to give fair concrete finish including stripping off and removing after completion of work as per specification	1500.00	SQM	107.00	160500.00
4	Providing and laying boulder sausage work including labour for filling properly the empty sausage crates with supply of boulders of size above 225mm and wire net of size 4mm thick and 150mm x 150mm mesh with hand packing after preperation of bed of placement , placing the crate in position , supply & carriage of bouldersfrom road stacks with a lead upto 150 meters etc. complete in all respect including stiching with wire the rest of sausage crate after fillinh up the crate with boulders and launching the crate in position if necessary and as directed by Engineer - in- charge.	3888	CUM	1250.00	4860000.00
	TOTAL				5578626.00

